

Graeagle Community Services District

P.O. Box 1414
Graeagle, CA 96103
gcsd96103@yahoo.com

To: Plan Holders
Graeagle Community Services District
THE GRAEAGLE CREEK PEDESTRIAN BRIDGE PROJECT

From: Daniel B. Bastian and GCS D Board

Subject: Addendum #1

Date: 1/17/2023

This Addendum #1 consists of 2 pages.

It is the responsibility of the Bidder to assure and guarantee by acknowledging the receipt of this Addendum in the Bid Form, that the Bidder has received the Addendum in its entirety, and that the Bidder accepts all conditions contained herein.

A. Appendix I, Page 224, 55-1.02E(7)(c)(i)(E)(5), Timber Decking: Said Section requires the bridge decking to be timber as specified. Please delete said section and replace with the following: "**55-1.02E(7)(c)(i)(E)(5), Decking.** The decking requirement is hereby changed to a 6" concrete deck to be placed by others. Include said concrete deck dead load in the structural design."

B. Bridge, Page 9: The bridge must be able to support a future watermain, sewer force main and two electrical conduits. It is anticipated that the loaded weight of such infrastructure will be less than or equal to 100 lbs./ft. Include said infrastructure dead load into the structural design of the bridge/abutments.

C. General Scope of Services, Page 12: The abutments must have sleeves constructed to allow for a water main, a sewer force main and two electrical conduits to pass through in a location under the bridge deck. Please anticipate installation steel sleeves for the following in each abutment: 18" for the water main, an 8" for the sewer force main and two 4" for the electrical conduit in your proposal.

D. General Scope of Services, Page 12: The bridge will be used by small equipment, such as golf carts. Also, during special events, the bridge may be loaded with pedestrians that far exceed usual foot traffic. Such loads are undetermined at this point in the Project. Please anticipate conservative live loads

for such uses in the structural design of the bridge/abutments. The final loading will be addressed after the project is awarded.

NOTE: This Addendum is to be signed by Bidder and submitted with the Bidder's Proposal. Use the attached Bid Schedule for your bid.

Dated: 1/17/2023



By:

Daniel B. Bastian

Distribution: All Plan Holders

Dated:

SIGNED: _____

(Bidder)

[END of ADDENDUM #1]